

NO.	ELEV.	DESCRIPTION	
1		92 IN X 144 IN FRP WET WELL	$\mathbb{I}$
	2000.00	RIM	7
	1988.00	BASE	1
2		92IN X 66 IN FRP VALVE VAULT	$\mathbb{I}$
	1994.50	BASE	$\mathbb{I}$
3	1994.00	IE - 16 IN INLET HUB FOR 12 IN SDR 35 PVC PIPE	7
		9:00 POSITION	
4	1996.00	IE - 6 IN SCH 10 STAINLESS STEEL OUTLET	
		3:00 POSITION	$\mathbb{I}$
5		HYDROMATIC S6LXP2000 PUMPS, 20 HP, 460V/3	
		EXPLOSION-PROOF, 600 GPM @ 60 FT TDH	
		**SHIPPED LOOSE**	
6		HYDROMATIC 6 IN MTM DISCHARGE ELBOW	
7		2 IN SCH 40 STAINLESS STEEL SLIDE RAILS	7
8		LEVEL TRANSDUCER & FLOAT SWITCHES	7
	1993.50	FLOAT SWITCH - REDUNDANT ON/HIGH LEVEL ALARM	
	1993.50	HIGH LEVEL ALARM	1
	1993.30	LAG PUMP ON	1
	1993.00	LEAD PUMP ON	1
	1991.00	PUMP(S) OFF	1
	1988.50	TRANSDUCER FACE	1
9		6 IN SCH 10 STAINLESS STEEL DISCHARGE MANIFOLD	7
10		2 IN SCH 40 PVC DRAIN	7
11		6 IN LEVER AND WEIGHT CHECK VALVE	7
12		6 IN RESILIENT SEAT GATE VALVE	7L
13		LADDER	
14		6 IN BADGER M3000 MAGMETER - REMOTE READOUT	7
15		EXHAUST FAN, 1/2 HP, 120V/1	7
16		ELECTRICAL HAND HOLE JUNCTION BOX ASSEMBLY	] }
		**SHIPPED LOOSE**	<u> </u>
17		300 PSF ALUMINUM HATCHES	
18		DUPLEX ALTERNATING COTROL PANEL (NOT SHOWN)	
		**SHIPPED LOOSE**	

CUSTOMER APPROVAL:

DATE:

BY THIS SIGNATURE, CUSTOMER INDICATES THAT HE HAS REVIEWED THIS SUBMITTAL DRAWING AND FOUND THAT IT MEETS ALL OF THE DESIGNER'S FUNCTIONAL REQUIREMENTS AND/OR SPECIFICATIONS. CUSTOMER HEREBY AUTHORIZES RC WORST & CO. INC. TO MANUFACTURE THE CUSTOM PRODUCT IN ACCORDANCEWITH THIS SUBMITTAL DRAWING.

AFS-STN-92-144-92-66-60-60-SS-EXT PACKAGED LIFT STATION - PROJECT NAME - QT 12345 COMPONENT DETAILS

3/15/16 1:36 RJK N/A

WWW.RCWORST.COM

625 BEST AVE 4444 S YELLOWSTONE HWY COEUR D'ALENE, ID 83814 IDAHO FALLS, ID 83402 PHONE 208.664.2133 208.529.6868